

Name of Work	SPECIAL REPAIR WORKS THE WORK IN OS PC/HC UNOCCUPIED QUARTERS AT THIRUCHULI IN VIRUDHUNAGAR DISTRICT - PART - 1				
S.No	Description of work	Qty	Rate	Per	Amount
1	Dismantling the Existing pressed tiles and weathering course etc...PWD SR P-22/23-24	40.10	41.80	Sqm	1676.18
2	Dismantling the RCC etc...PWD SR P-22/23-24	5.60	3917.00	Cum	21935.20
3	Dismantling and clearing away carefully stacking material in brick work etc...PWD SR P-21/23-24 (SE)	17.00	339.00 311.80	Cum	5763.00 5300.60
4	Form work using MS sheet				0.00
	b.plain surface such as roof slab, beams, lintels etc....	44.80	946.62	Sqm	42408.58
5	Standardised concrete mix m-20 grade etc....				
	d.Second floor	5.60	8498.56	Cum	47591.94
6	Fabrication of Mild steel / RTS grills	0.56	88873.50	MT	49769.16
7	Brick work in C.M. 1:6 using Kiln Burnt Country bricks of size 22 x 11 x 7 cm (8 3/4" x 4 1/4" x 2 3/4") C.Second floor	2.00	6995.81	Cum	13991.62
8	Brick Partion in C.M. 1:4 110mm thick using Kiln Burnt Country bricks of size 22 x 11 x 7 cm (8 3/4" x 4 1/4" x 2 3/4") C.Second floor	22.00 21.93	850.78	Sqm	18717.16 18657.61
9	Special ceiling plastering in cm 1:3, 10mm tk etc...	46.10	288.61 289.11	Sqm	13304.93 13327.97
10	Plastering in cm 1:5, 12mm tk etc....	63.50	253.17	Sqm	16076.30
11	White washing 3 coats (slaked)	46.10	45.28	Sqm	2087.41
12	PVC SWR 110 mm dia Rain water pipe	6.00	343.11	Rmt	2058.66
	Sub Total - I				234881.23
	Add CGST & SGST @ 18%				42278.62
	SUB Total - II				277159.85
	Labour charges @ 1%				2771.59
	Supervision charges @ 7.5%				20786.99
	Grand Total				300295.65
				Say	3.01 Lakhs

Say Rs. 3,01,000/-

P. G. M. M. V.
22/5/23

ACE 22-5-23

P. G. M. M. V.
26/05/23
TA

26/05/23
20
EXECUTIVE ENGINEER
TAMILNADU POLICE HOUSING CORPORATION LTD
TIRUNELVELI DIVISION
TIRUNELVELI - 627 002