SE/South Circle. Agt. No. 29/2023-2024 FILE No. DB/SC/1479/2023 REPORT ACCOMPANYING SLIP FOR LUMPSUM AGREEMENT (FOR OFFICE USE ONLY)

TAMILNADU POLICE HOUSING CORPORATION LTD., SOUTH CIRCLE, MADURAI – 625 014.

NAME OF PROJECT Police – Buildings – Announcement made by

the Hon'ble Chief Minister on the Floor of the Assembly during the Police demand for the year 2022-2023 – Special repair works in 751 Unoccupied quarters in Various District

751 Unoccupied quarters in Various Distric

Special repair works for the 18 Nos. of PC/HC quarters at Sivakasi in Virudhunagar

District.

ESTIMATE AMOUNT : ₹ 25,52,700/- × .

ESTIMATE No. : SE SC.ER.No.04/2023-2024

ESTIMATE AMOUNT PUT IN TENDER : ₹24,03,443.53 (2023-2024) ₹

(Including the GST @18%)

TENDER VALUE : ₹20,67,135.33 (Including the GST @18%)

LESS AMOUNT : (-) ₹ 3,36,308.20

LESS PERCENTAGE : (-) 13.99 %

TENDER ACCEPTED BY WHOM : The Superintending Engineer

TNPHC Ltd., South Circle, Madurai -14

NAME OF THE CONTRACTOR : Thiru. S. MASANAMUTHU

No. OF ITEMS IN THE AGREEMENT : 40 (Forty only)

No. OF PAGES IN THE AGREEMENT : 60 (Sixty only)

No. OF CORRECTIONS IN THE

NAME OF WORK

AGREEMENT : Nil

SUPERINTENDING ENGINEER SOUTH CIRCLE, TNPHC LTD.,





தமிழ்நாடு तमिलनाडु TAMILNADU 13, 06, 2023

20 nonon 235

CK 547424

செ. சக்கி வடிவேல் சா.ப.அ. முற்றிவந்தாள் முகவர் கு.படகால்

TAMIL NADU POLICE HOUSING CORPORATION MANUFED., \$\\$6/8555/82 SOUTH CIRCLE, MADURAI - 625 014.

ARTICLES OF AGREEMENT

ARTICLES OF AGREEMENT made this

an Limited (hereinafter called the Corporati

BETWEEN the Tamil Nadu Police Housing Corporation Limited, (hereinafter called the Corporation Limited which expression shall where the context so admits include its successors in office and assigns) of the ONE PART and

Thiru. S. MASANAMUTHU, NO. 4/1/49, OLD POST OFFICE STREET, AYIKUDI (VIA) KILANGADU (POST), TENKASI DISTRICT – 627 852.

(Hereinafter called the contractor which expression shall where the context so admits include its heirs, executors, administrators and legal representatives) of the OTHER PART

No. of corrections

3 87 89

TAMIL NADU POLICE POUSING CORPORATION LIMITED., SOUTH CIRCLE, MADURAI – 625 014.

ARTICLES OF AGREEMENT

ARTICLES OF AGREEMENT made this

day of

BETWEEN the Tamil Nadu Police Housing Corporation Limited, (hereinafter called the Corporation Limited which expression shall where the context so admits include its successors in office and assigns) of the ONE PART and

Thiru. S. MASANAMUTHU,

NO. 4/1/49, OLD POST OFFICE STREET,

AYIKUDI (VIA)

KILANGADU (POST)

TENKASI DISTRICT 4 627 852.

(Hereinafter called the contractor which expression shall where the context so admits include its heirs, executors, administrators and legal representatives) of the OTHER PART

WHEREAS the corporation Limited is desirous of Special repair works for the 18 Nos. of PC/HC quarters at Sivakasi in Virudhunagar District and have caused an estimate of probable quantities contained in schedule A, drawings and specifications describing the work to be done to be prepared.

AND WHEREAS the said schedule A, drawings (schedule B) and the specifications (schedule C) and other schedules herewith annexed have been signed by or on behalf of the parties hereto.

AND WHEREAS the contractor has agreed to the retention, by the Corporation Limited of earnest money (with GST) of ₹ 21/800/- (Rupees twenty one thousand and eight hundred only) in the form of Demand Draft No.170565 Dated:26.05.2023 issued by Indian Overseas Bank, Ayikudi-1378 paid by him when he submitted his tender, as security for the due fulfillment of the contract to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited.

AND WHEREAS the Contractor has remitted a further sum of ₹ 68,000/- (Rupees sixty eight thousand only) paid in the form of National (Small) Savings Schemes Pass Book Issued by Post Office Ayikudi-S.O, Department of Posts, India and the details are as follows

Contractor

No. of corrections

1. A/c No. 020079908491 Dated: 24.06.2023

2. A/C No. 020079908632 Dated: 24.06.2023

3. A/C No. 020080849802 Dated: 05.07.2023

24,000.00

Total

against the balance of the security deposit and additional security deposit amount of ₹ 67,700/- (with GST) for the due fulfillment of the contract to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited

AND WHEREAS the Contractor has also signed a copy of the Tamilnadu Building practice and the addenda volume there to maintained in the office of the Superintending Engineer /South Circle Tamil Nadu Police Housing Corporation Limited in acknowledgement of being bound by all the conditions of the clauses of the general conditions of contract and all the standard specifications for items of works described by a standard Specification number in Schedule - A.

AND WHEREAS the contractor has agreed to execute upon and subject to the conditions set forth in the conditions of contract of the Tamil Nadu Building Practice and such other conditions as are contained in all the specifications forming part of this contract (hereinafter referred to as "the said conditions") the work shown upon the drawings and described in the said specifications and set forth in Schedule -A as the "Probable Quantities" and comply with the rate of progress noted at the end of this ARTICLES OF AGREEMENT, for a sum of ₹ 20,67,135.33 (Rupees twenty lakhs sixty seven thousand one hundred and thirty five and paise thirty three only) or such other sum as may be arrived at under the clause of the General conditions of contract relating to "Payment on lumpsum basis or by final measurement at Unit Prices"

Now it is hereby agreed as follows:

1. In consideration of the payment of the said sum of ₹ 20,67,135.33 (Rupees twenty lakhs sixty seven thousand one hundred and thirty five and paise thirty three only) or such other sum as may be arrived at under the clause of the General conditions of contract relating to Payment on lumpsum basis or by final measurement at unit prices, the contractor will upon and subject to the said conditions execute and complete the works shown upon the said drawings and described in the said specifications and to the extent of the probable quantities shown in schedule A, with such variations by way of alterations of, additions to, or deductions from, the said works and method of payment there for are as provided for in the said conditions.

S-Lardon No. of corrections



- 2. The term "Corporation Limited" in the said conditions shall mean the Tamil Nadu Police Housing Corporation Limited or any officer of the Corporation Limited incharge of the works who shall be competent to exercise all the powers and privileges reserved herein, in favour of the Corporation Limited with the previous sanction of the Corporation Limited or any other officer authorized by the Corporation Limited.
- 3. The arbitrator for fulfilling the duties set forth in the arbitration clause of the General conditions of contract shall be the Chief Engineer, Tamil Nadu Police Housing Corporation Limited upto value of claims of Rs. 50,000/- If the value of claims exceeds Rs. 50,000/- the matter shall be referred to the court having jurisdiction over Tamil Nadu state.
- 4. Time shall be considered as the essence of the agreement and the Contractor hereby agrees to commence the work as soon as this agreement is accepted by the Corporation Limited or any other officer authorized by the Corporation Limited and the site (or premises) is handed over to them as provided for in the said conditions and agrees to complete the work within FIVE months from the date of such handing over the site (or premises) and to show progress as defined in the tabular statement "RATE OF PROGRESS" below, subject nevertheless to the provisions for extension of time contained in clause 56 of the General conditions of contract.

Rate of Progress

The following rate of progress and proportionate value of work done from time to time, as will be indicated by the Executive Engineer's Certificate of the value of work done will be required.

Date of commencement of this programme will be the date on which the site (or premises) is handed over to the Contractor.

Period after date of	Percentage of work completed
Commencement	(Based on Contract lumpsum amount)
(1)	(2)
I – Month	20 %
II - Month	40 % 7
III - Month	60 % / 80 % /
IV - Month	80 % -
V – Month	100 %

S- 24 ranson Q > Contractor

Nø. of corrections

- 5. "The said conditions" shall be read and construed as forming part of this agreement and the parties hereto will respectively abide by and submit themselves to the conditions and stipulations and perform the agreements on their parts, respectively.
- 6. Upon the terms and conditions of this agreement being fulfilled and performed to the satisfaction of the Corporation Limited or any other officer authorized by the Corporation Limited, the security deposited by the contractor as herein before recited or such portion thereof as they may be entitled to under the said conditions shall be returned to the contractor.

IN WITNESS WHERE OF the contractor Thiru. S. MASANAMUTHU has hereunto set his hand and the Superintending Engineer/South Circle of Tamil Nadu Police Housing Corporation Limited on behalf of the Corporation Limited have hereunto set his hand, the day and year first above written.

Signed by the Contractor

3.20 manos 93

Address

: Thiru. S. MASANAMUTHU, >

NO. 4/1/49, OLD POST OFFICE STREET,

AYIKUDI (VIA) 🗡

KILANGADU (POST), TENKASI DISTRICT - 627 852.

8-7+ Bown of 7-5

TAMIL NADU POLICE HOUSING CORPORATION LIMITED

No.1, INSPECTOR QUARTERS, TSP 6 TH BATTALION CAMPUS, NEW NATHAM ROAD, MADURAI – 625014.

Schedule 'A'

- A. The quantities given here are those upon which the lumpsum tender cost of the work is based, but they are subject to alterations, omissions, deductions or additions are provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates excluding GST amount quoted are those governing payments for extras or deductions or omissions according to the conditions of the contract asset forth in the general conditions of the contract of the Tamil Nadu Building practice and other conditions or specifications of this contract.
- B. It is to be expressly understood that the measured work is to be taken net (not withstanding any custom of practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Chief Engineer and the cost calculated-by measurement or Weight at the respective prices without any additional charges for any necessary or contingent works connected herewith. The rates quoted excluding GST amount are for works in situ and complete in every respect.
- C. Unavoidable delays may entail in rate instances, for delays beyond 3 months after execution of agreement, offer may be with drawn/cancelled, validity shall be however optional subject to mutual consent by the contractor and TNPHC at agreed rates without extras.
- D. As a result of continuous improvements contemplated by the TNPHC in layouts/type design, substantial variations might occur in one more items. The tenderer will be expected to adopt such modifications whenever necessitated and ordered for.
- E. If rarely owning to non availability of vacant lands in the site mentioned in the notification change of site either partly or wholly is warranted, the tenderer shall accept to execute work accordingly as may be necessitated and ordered for at agreed rates or derived rates.

5-24Mnong 3

NO. OF CORRECTIONS

ME OF WORK: SPECIAL REPAIR WORKS FOR THE 18 NOS. OF PC/HC QUARTERS AT SIVAKASI IN VIRUDHUNAGAR DISTRICT

		FIGURES AND IN WORDS	AND IN WORDS	
2 263.25 Sq.M.	DISMANTLING CLEARING AWAY AND CAREFULLY STACKING MATERIALS USEFUL FOR RE-USE OF PRESSED TILES IN CEMENT MORTAR AND WEATHERING COURSE WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.	- /	5 1.sq.m. (ONE SQUARE METRE)	6 6054.75
1550.90 Sq.M.	FROM THE EXISTING WALL / CEILING WITHOUT	(Rupees seven and paise fifty	1.Sq.M. (ONE SQUARE METRE)	11631.75
13.10 Cu.M.			1.Cu.M. (ONE CUBIC METRE)	52400.00
	PROVIDING CUDDAPPAH SLAB OF 40MM THICK FINISHING WITH TWO SIDES FOR CUPBOARD, SUNSHADE, WARD ROBES, SHELVES, SIDE SLABS OF BOXING AROUND WINDOWS, SINK AND OTHER SIMILAR WORKS INCLUDING FINISHING AND FIXING IN POSITION COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS ETC., COMPLETE IN THE FOLLOWING FLOORS (MEASUREMENT WILL BE TAKEN INCLUDING BEARING ALSO) AS DIRECTED BY THE DEPARTMENTAL OFFICERS (QUALITY OF CUDDAPPAH SLAB SHALL BE GOT APPROVED BY THE EXECUTIVE ENGINEER., SUPERINTENDING ENGINEER., CHIEF ENGINEER, BEFORE USE IN WORKS. CUDDAPPAH SUNSHADES SHALL BE PROVIDED WITH CUDDAPPAH BEEDING OF REQUIRED SIZE TO PROVIDE RAIN WATER IN THE ROOMS WITHOUT ANY EXTRA COST)			
21.30 Sg.M.	(c) IN SECOND FLOOR	Rs.629.00 / (Rupees six hundred and twenty nine only)	1.Sq.M. (ONE SQUARE METRE)	13397.70
1.10 Cu.M.	OF CRUSHED STONE SAND) WITH ADMIXTURE	(Rupees six thousand eight hundred and four only)	1.Cu.M. (ONE CUBIC METRE)	7484.40
	1550.90 Sq.M. 13.10 Cu.M.	STACKING MATERIALS USEFUL FOR RE-USE OF PRESSED TILES IN CEMENT MORTAR AND WEATHERING COURSE WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. 1550.90 Sq.M. CLEAN REMOVAL OF CEMENT PLASTER SURFACE FROM THE EXISTING WALL / CEILING WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. 13.10 Cu.M. DISMANTLING CLEARING AWAY AND CAREFULLY STACKING MATERIALS SEPIL FOR RE-USE OF REINFORCEMENT CEMENT CONCRETE WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. 13.10 Cu.M. PROVIDING CUDDAPPAH SLAB OF 40MM THICK FINISHING WITH TWO SLOBE FOR CUPBOARD, SUNSHANDE, WARD FORDES, SHELVES, SIDE SLABS OF BOXING AROUND WINDOWS, SINK AND OTHER SIMILAR WORKS INCLUDING FINISHING AND FIXING IN POSITION COMPLYING WITH TWO SLOBE FOR CUPBOARD SPECIFICATIONS ETC., COMPLETE IN THE FOLLOWING FLOORS (MEASUREMENT WILL BE TRACEN INCLUDING BEARING ALSO) AS DIRECTED BY THE DEPARTMENTAL OFFICERS (QUALITY OF CUDDAPPAH SLAB SHALL BE GOT APPROVED BY THE EXECUTIVE ENGINEER, SUPERINTENDING ENGINEER, CHIEF ENGINEER, CHIEF ENGINEER, COMPRESED STALL BE PROVIDED WITH ELEVANT STANDARD PRO	TACKING MATERIALS USEFUL FOR RE-USE OF (Rupees twenty three only) PRESSED TILES IN CEMENT MORTAR AND WEATHERING COURSE WITHOUT AFFECTING THE ADACENT STRUCTURES, MULDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DEMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMMETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. 1550.90 Sq.M. CLEAN REMOVAL OF CEMENT PLASTER SURFACE FROM THE EXISTING WALL / CEILING WITHOUT THE COST OF REQUIRED TOOLS AND PLANTS AND SOME OF RECOURSED TOOLS AND PLANTS AND DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS 13.10 Cu.M. DISMANTLING CLEARING AWAY AND CAREFULLY STACKING MATERIALS USEFUL FOR RE-USE OF REINFORCEMENT CEMENT CONCRETE WITHOUT AFFECTINS THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLETE AND AS DIRECTED BY THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC., ALL COMPLING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC. ALL COMPLING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC. ALL COMPLING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC. ALL COMPLING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC. ALL COMPLING WITH THE POLLOWING THE SITE OF TH	STACKING MATERIALS USEFUL FOR RE-USE OF (Rippes tyenty three only) PRESSED TILES IN CEMENT MORTAR AND WEATHERING COURSE WITHOUT AFFECTING THE ADJACENT STRUCTURES, INCLUDING THE COST OF REQUIRED TOOLS AND PLANTS AND SCAFFOLDING IS NECESSARY AND CLEARING THE DISMANTED MATERIALS AWAY FROM THE STEETC, ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. 1550-90 Sq.M. CLEAN REMOVAL OF CEMENT PLASTER SURFACE FROM THE EXISTING WALL / CEILING MYTHOUT APPETITION THE ADJACENT STRUCTURES, NECULIARY FROM THE EXISTING WALL / CEILING MYTHOUT APPETITION THE ADJACENT STRUCTURES, NECULIARY FROM THE EXISTING WALL / CEILING MYTHOUT APPETITION THE ADJACENT STRUCTURES, NECULIARY FROM THE EXISTING WALL / CEILING MYTHOUT APPETITION THE ADJACENT STRUCTURES, NECULIARY FROM THE ADJACENT STRUCTURES, NECULIARY AND SCAFFOLDING IF NECESSARY AND CLEARING THE DISMANTLED MATERIALS AWAY FROM THE SITE ETC. ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS 13.10 Cu.M. 13.10 Cu.M. 13.10 Cu.M. 15.20 M. 16.20 M. 17.20 M. 17.20 M. 18.20 M. 19.20 M. 19.20 M. 19.20 M. 19.20 M. 19.20 M. 10.20

S- 2 moss So

NO. OF CORRECTIONS

Special repair works at Signaturi

10	6	Special repair works at	Sayakan		PAGE - 2
.NO.	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS 5	AMOUNT
6	1 1	SPECIAL CEILING PLASTERING IN CM 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) WITH ADMIXTURE 10MM THICK FOR BOTTOM OF ROOF, STAIR, WAIST, LANDING AND SUNSHADES IN ALL FLOORS FINISHED WITH NEAT CEMENT INCLUDING HACKING THE AREAS, PROVIDING BAND CORNICE, SCAFFOLDING, CURING ETC., COMPLETE.	Rs.250.00 × / (Rupees two hundred and fifty	1.Sq.M. (ONE SQUARE METRE)	90968.60
7/	ر 1385.30 Sq.M.	PLASTERING WITH CM 1:5 (ONE OF CEMENT AND	Rs.200.00 🗡 🥖	1.Sq.M.	277060.0
	7		(Rupees two hundred only)	(ONE SQUARE METRE)	7
8	30 NOS.X	SUPPLYING AND FIXING OF 4'18 WATTS CRYSTAL LED TUBE LIGHT AND FIXING THE TUBE LIGHT		1.NO. (EACH)	20430.0
	7	FITTINGS ON TEAK WOOD ROUND BLOCKS OF 75MM DIA OR 40MM DEEP SUSPENDED FROM CEILING OR MOUNTED ON THE WALL INCLUDING COST OF ALL MATERIALS AND LABOUR FOR FIXING IN POSITION ETC. ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE ENTIRE TUBE LIGHT FITTINGS SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	one only)	*	
9	40 NOS.	SUPPLYING AND FIXING OF 9 WATTS LED BULB OF BEST QUALITY INCLUDING COST OF MATERIAL AND FIXING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS, (THE QUALITY OF THE 9 W LED BULB SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	(Rupees one hundred and forty	1.NO. (EACH)	5680.0
10		SUPPLYING AND DELIVERY OF FOLLOWING ELECTRIC CEILING FAN WITH ISI MARK WITH BLADES AND DOUBLE BALL BEARING, CAPACITOR, ETC., COMPLETI WITH 300MM DOWN ROD, CANOPIES, CAPACITOR SHACKLE BLADES WITH ELECTRONIC DIMMER SUITABLE FOR OPERATION ON 230 VOLTS 50 HT SINGLE PHASE AC SUPPLY CONFORMING TO IS. NO.374/79 AND PROVIDED WITH INSULATION. (THE BRAND SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE SUPPLY MADE).			
	16 NOS.X	(a) 48" ELECTRIC FAN 1200MM SWEEP	Rs.1500.00 (Rupees one thousand and five hundred only)	1.NO. (EACH)	× 24000.
11	16 NOS. >	CHARGES FOR ASSEMBLING AND FIXING OF CEILIN FAN OF DIFFERENT SWEEP WITH NECESSAR CONNECTIONS AND FIXING OF FAN REGULATOR OTHE EXISTING BOARD ETC., ALL COMPLET (EXCLUDING COST OF FAN)	Y (Rupees five hundred and eighty N four only)	1.NO (EACH)	9344.
		£			468882.

S- LAND NOOD & CONTRACTOR

NO. OF CORRECTIONS

Special repair works at Shaller

S.NC.	QUANTITY 2	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	6 468882.60
12	7	SUPPLYING AND FIXING OF 110MM DIA PVC SWR PIPE WITH ISI MARK CONFIRMING TO IS 13952:1992- TYPE 'A' FOR RAIN WATER DOWN FALL PIPE WITH RELEVANT SPECIALS SUCH AS GRATINGS, SHOES, BENDS, OFFSETS CONFIRMING TO IS 14735 INCLUDING JOINTING WITH SEAL RING CONFIRMING IS 5382 WITH LEAVING A GAP ABOUT 10MM TO ALLOW THERMAL EXPANSION WITH NECESSARY CLAMPS, TEAK WOOD PLUGS, ETC., OF APPROVED QUALITY AND INCLUDING FIXING C.I. GRATINGS AT THE JUNCTION OF PARAPET AND FLOOR OR ROOF SLAB ETC., INCLUDING FINISHING ETC., COMPLETE COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS.	(Rupees three hundred and fifty three only)	1. Rmt. (ONE RUNNING METRE)	7766.00
13		SUPPLYING, LAYING, FIXING AND JOINTING THE FOLLOWING DIA PVC PIPES AS PER ASTMD - 1785 OF SCHEDULE 40 OF WALL THICKNESS NOT LESS THAN THE SPECIFIED IN IS 4985 SUITABLE FOR PLUMBING BY THREADING OF WALL THICKNESS INCLUDING THE COST OF SUITABLE PVC/IG SPECIALS /GM SPECIALS LIKE ELBOW, TEE REDUCERS, PLUG, UNION, BEND, COUPLER, NIPPLE/ GM GATE VALVE, CHECK AND WHEEL VALVE ETC., WHEREVER REQUIRED ABOVE THE GROUND LEVEL INCLUDING THE COST OF TEFLON TAPE, SPECIAL CLAMPS, NAILS, ETC., FIXING ON WALL TO THE PROPER GRADIENT AND ALIGNMENT AND REDOING THE CHIPPED OF MASONRY ETC., AS DIRECTED BY THE DEPARTMENTAL OFFICERS.			
	47.50 Rmt. X	(a) 32MM ASTM D SCHEDULE 40 THREADED PVC PIPE WITH NECESSARY PVC/GI/GM SPECIALS	Rs.253.00 (Rupees two hundred and fifty three only)	1.Rmt. (ONE RUNNING METRE)	12017.50
	66.00 Rmt. X	(b) 25MM ASTM D SCHEDULE 40 THREADED PVC PIPE WITH NECESSARY PVC/GI/GM SPECIALS	Rs.240.00 X (Rupees two hundred and forty only)	1.Rmt. (ONE RUNNING METRE)	15840.00
	38.00 Rmt.	(c) 20MM ASTM D SCHEDULE 40 THREADED PVC PIPE WITH NECESSARY PVC/GI/GM SPECIALS	Rs.233.00 (Rupees two hundred and thirty three only)	1.Rmt. (ONE RUNNING METRE)	8854.00
14	22 NOS.	SUPPLYING AND FIXING OF HALF TURN BRASS COR- CP LONG BODY TAP OF 15MM DIA OF BEST QUALIT INCLUDING COST OF HALF TURN CP TAP WITH INCLUDING SPECIALS AND LABOUR FOR FIXING ETC ALL COMPLETE AND AS DIRECTED BY TH DEPARTMENTAL OFFICERS, (THE QUALITY AND BRAN) SHOULD BE GOT APPROVED FROM THE EXECUTIV ENGINEER BEFORE USE)	(Rupees five hundred and four only)	1.NO. (EACH)	11088.00
15	10 NOS.	SUPPLYING AND FIXING OF HALF TURN BRASS COR CP SHORT BODY TAP OF 15MM DIA OF BEST QUALIT INCLUDING COST OF HALF TURN CP TAP WIT REQUIRED SPECIALS AND LABOUR FOR FIXING ETC ALL COMPLETE AND AS DIRECTED BY TH DEPARTMENTAL OFFICERS. (THE QUALITY AND BRAN SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	(Rupees four hundred and fifty three only)	1.NO. (EACH)	4530.00
		- 1			528978.10







ON.	QUANTITY.	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT 6
16	1	SUPPLYING AND FIXING OF 4 MM THICK PIN HEADED GLASS PANELS WITH ALUMINIUM ANODIZED 'U' SHAPE BEADING OF SIZE 12X12 MM WITH 107 GRAM IN AVERAGE WEIGHT FOR 1 M LENGTH WITH ALUMINIUM BOLTS AND NUTS FOR THE SHUTTERS OF THE STEEL WINDOWS ALREADY SUPPLIED TO SUIT ALL THE SIZE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (THE QUALITY OF GLASS AND ALUMINIUM BEEDING SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	(Rupees seven hundred and sixty	1.Sq.M. (ONE SQUARE METRE)	528978.10 7848.60
17	11.40 Sq.M.	FRAME OF SIZE 50X47MM WITH A WALL THICKNESS OF 5MM, MADE OUT OF EXTRUDED 5MM RIGID UPVC FOAM SHEET, MITERED AT TWO CORNERS AND JOINED WITH 2 NOS. OF 150MM LONG BRACKETS OF 15X15MM M.S SQUARE TUBE. THE TWO VERTICAL AND HORIZONTAL DOOR PROFILES ARE TO BE REINFORCED WITH 19X19MM M.S SQUARE TUBE OF 19 GAUGES WITH 19X19MM M.S SQUARE TUBE OF 15 GAUGES WITH 19X19MM M.S SQUARE TUBE OF 19 GAUGE MITH 19X19M FOR 5X SCREWS TO BE PROVIDED FOR EACH VERTICAL MEMBER AND MINIMUM 2 NOS. FOR HORIZONTAL MEMBER AND MINIMUM 2 NOS. FOR HORIZONTAL MEMBER ETC., PROVIDING AND FIXING OF 30MM THICK FACTORY MADE DOOR SHUTTER WITH UNPLASTICIZED POLYVINYL CHLORIDE (UPVC) SOLIL PANEL FOAM SHEET, STRUCTURED WITH M.S.TUBE OF 19 GAUGE THICKNESS AND SIZE 19MM X 19MM FOR STYLES AND 15MM X 15MM FOR TOP RAIL AND ROTTOR RAIL. PANELLING OF 5MM THICK UPVC ONE SID PRINTED LAMINATION SINGLE SHEET TO BE FITTED IN THE M.S.FRAME WELDED / SEALED TO THE STYLES AND AND ASM THICK UPVC C'C CHANNEL OF 30MMX50MM AND 5MM THICK UPVC C'C CHANNEL OF SIDE AND 10MM (5MM X NOS.) THICK, 20MM WIDDE CROSS UPVC SHEET AS GAINSERT FOR TOP RAIL AND BOTTOM RAIL, AND JOINE! TOGETHER WITH PVC SOLVENT CEMENT ADHESIVE. AN ADDITIONAL 5MM THICK UPVC SIRIP OF 20MM WIDTH IS TO 9E STUCK ON THE INTERIOR SIDE OF TH C'C CHANNEL USING PVC SOLVENT CEMENT ADHESIVE THE COST AND LABOUR CHARGES FOR FIXING OF THE COST AND LABOUR	(Rupees three thousand and three hundred only)	1.Sq.M. (ONE SQUARE METRE)	37620.00
18	2 NOS.	FITTING SUCH AS 1 NO, 4" TOWER BOLT, 1 NO.3 ALDROP, 2 NOS, 6" FLAT 'D' TYPE HANDLE, ETC AR INCLUDED. THE FITTING PROVIDED SHALL BEAR IS MARKS. TO ENSURE THE GENUINITY OF PRODUCT, THOOR SET SHOULD HAVE 4 NUMBERS, COMANUFACTURER'S LOGO HOLOGRAM OF APPROVE BRAND, FACH AT FRAME, STYLE, RAIL AND INNE PANEL, (THE QUALITY AND BRAND OF DOOR SHUTTE AND FURTURE FITTINGS SHOULD BE GOT APPROVE BY THE EXECUTIVE ENGINEER BEFORE USE) SUPPLYING AND FIXING OF INDIAN WATER CLOSE	RS.3421.00 (Rupees three thousand four hundred and twenty one only) Tr., OF OP OP UT IG,	1.NO. (EACH)	6842.0





S.NO	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES	AMOUNT
1	2	3	FIGURES AND IN WORDS	5	6
19	11	FINISHING TOP OF ROOF WITH ONE COURSE OF HYDRAULIC PRESSED TILES OF APPROVED SUPERIOR QUALITY OF SIZE 23CMX 23CMX20MM THICK LAID OVER WEATHERING COURSE IN CM 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 12MM THICK MIXED WITH WATER PROOFING COMPOUND AT 2% BY WEIGHT OF CEMENT USED AND POINTED NEATLY WITH THE SAME CEMENT MORTAR MIXED WITH WATER PROOFING COMPOUND INCLUDING CURING ETC., AS PER STANDARD SPECIFICATIONS. (THE QUALITY OF TILES SHALL BE GOT APPROVED FROM THE EE BEFORE USE)	(Rupees nine hundred and ninety	1.Sq.M. (ONE SQUARE METRE)	260667.00
20	231.10 Sq.M.	POINTING THE PRESSED TILES WITH CM 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) INCLUDING CURING ETC., AS PER STANDARD SPECIFICATIONS, (THE QUALITY OF THE TILES SHALL BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE.)	(Rupees two hundred and eighty	1.Sq.M. (ONE SQUARE METRE)	64708.00
21		PRECAST CEMENT CONCRETE JALLY VENTILATOR IN STANDARDISED CONCRETE MIX M-20 GRADE IN ACCORDANCE WITH IS: 456 - 2000 USING 20MM AND DOWNGRADED HARD BROKEN STONE JELLY WITH ADMIXTURE FOR THE ABOVE RCC ITEM OF WORK WITHOUT VIBRATING HARGES EXCLUDING THE COST AND FABRICATION OF REINFORCEMENT GRILLS BUT INCLUDING PRECASTING, MOULDING, CURING, FINISHING AND FIXING IN POSITION COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS ETC., COMPLETE IN THE FOLLOWING FLOORS.			
	6.00 Sq.M.	(c) IN SECOND FLOOR	Rs.2800.00 X // (Rupees two thousand and eight hundred only)	1.Sq.M. (ONE SQUARE METRE)	16800.00
22	214.20 KG			1.KG. (ONE KILOGRAM)	14137.20
		/- t			/
23	196.60 Sq.M.	PAINTING THE OLD WOOD WORK WITH TWO COATS OF APPROVED FIRST CLASS SYNTHETIC ENAMEL READY MIXED PAINT INCLUDING THOROUGH SCRAPPING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS (THE QUALITY AND THI SHADE OF PAINT SHOULD BE GOT APPROVED BY THE	(Rupees one hundred and forty	1.Sq.M. (ONE SQUARE METRE)	28507.00
		EXECUTIVE ENGINEER BEFORE USE)			

E. Lovenson



Special repair works at Sivakusi

N/S	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
	2	3	4	5	6 966107.90
4	4 ×	PAINTING THE OLD IRON WORK WITH TWO COATS AND OTHER SIMILAR WORKS SUCH AS PVC / ASTM PIPES, KERB STONE AND GRILLS WITH TWO COATS OF APPROVED FIRST CLASS SYNTHETIC ENAMEL READY MIXED PAINT INCLUDING THOROUGH SCRAPPING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS (THE QUALITY AND THE BRAND OF PAINT SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE)	(Rupees one hundred and forty one only)	1.Sq.M. (ONE SQUARE METRE)	11477.40
25	6.20 Sq.M.	PAINTING THE NEW IRON WORK AND OTHER SIMILAR WORKS SUCH AS PVC / ASTM PIPES, KERE STONE AND GRILLS WITH TWO COATS OF APPROVED FIRST CLASS SYNTHETIC ENAMEL READY MIXED PAINT OF APPROVED QUALITY AND BRAND, THE PAINT SHOULD BE SUPPLIED BY THE CONTRACTOR AT HIS OWN COST, (THE QUALITY AND THE BRAND OF PAINT SHOULD BE GOT APPROVED BY THE EXECUTIVE ENGINEER BEFORE USE) COMPLYING WITH RELEVANT STANDARD SPECIFICATIONS.	(Rupees one hundred and forty only)	1.Sq.M. (ONE SQUARE METRE)	868.00
26	234.60 Sq.M.	WHITE WASHING THREE COATS USING CLEAN SHELL LIME SLAKED INCLUDING COST OF LIME, GUMBLUE, BRUSHES, INCLUDING SCAFFOLDING ETC COMPLETE IN ALL RESPECTS.	(Rupees forty five only)	1.Sq.M. (ONE SQUARE METRE)	10557.00
27	497.90 Sq.M.	PAINTING PRIMER COAT USING APPROVED QUALIT OF WHITE CEMENT OVER THE CEMENT PLASTERED CONCRETE NEW WALL SURFACES, CEILING OR OTHE SIMILAR WORKS INCLUDING COST OF WHITE CEMEN PUTTY, BRUSHES, WATERING, CURING, ETC., AL COMPLETE AND AS DIRECTED BY THE DEPARTMENTA OFFICERS.	(Rupees fifty five only)	1.Sq.M. (ONE SQUARE METRE)	27384.50
28	2003.00 Sq.M.	PAINTING THE OLD WALLS WITH TWO COATS OF OBOUND DISTEMPER OVER EXISTING WALL SURFACE INCLUDING THOROUGH SCRAPPING INCLUDING COOP PAINTS, PUTTY, BRUSHES, WATERING, CURIN ETC., ALL COMPLETE AS DIRECTED BY THE DEPARTMENTAL OFFICERS (PAINTS AND ITS SHAUT S	ST (Rupees one hundred only) ST G, HE DE	1.Sq.M. (ONE SQUARE METRE)	200300.0
29	887.50 Sq.M.,	PAINTING THE NEW WALLS WITH TWO COATS APPROVED BEST READY MIXED EXTERIOR EMULSION PAINT IN ADDITION TO ONE COAT APPROVED SPECIAL PRIMER COAT FOR OUTER WA OVER CEMENT PLASTERED WALL SURFACES A CEILING INCLUDING COST OF EXTERIOR EMULSIPAINT, PUTTY, BRUSHES ETC., ALL COMPLETE AND DIRECTED BY THE DEPARTMENTAL OFFICERS (TEXTERIOR EMULSION PAINT AND ITS SHADE A SPECIAL PRIMER SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USING)	OF (Rupees two hundred only) OF JLL ND ON AS HE	1.Sq.M. (ONE SQUARE METRE)	177500.0
		1			

S-Jorgana 3



Special 1	epair	works	aί	Sivakas	i.
-----------	-------	-------	----	---------	----

24	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1 /	2	3	4	5	6 1394194.80
30	12.50 Rmt.	SUPPLYING AND FIXING THE FOLLOWING DIA PVC (SWR) PIPE WITH ISI MARK CONFIRMING TO IS 13952:1992- TYPE 'B' FOR SOIL LINE WITH RELEVANT SPECIALS CONFIRMING TO IS 14735 INCLUDING JOINTING WITH SEAL RING CONFIRMING TO IS 5382 WITH LEAVING A GAP ABOUT 10MM TO ALLOW THERMAL EXPANSION, FIXING THE PIPES INTO WALLS WITH NECESSARY WOODEN PLUG, SCREWS, HOLDING WHEREVER NECESSARY AND MAKING GOOD OF THE DISMANTLED PORTION WITH NECESSARY CONNECTIONS TO SANITARY FITTINGS ETC., COMPLETE IN ALL RESPECTS AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (a)110MM DIA PVC SWR PIPE INCLUDING ALL REQUIRED PVC SPECIALS ETC., ALL COMPLETE.,	Rs.731.00 (Rupees seven hundred and thirty one only)	1.Rmt. (ONE RUNNING METRE)	9137.50
31		PROVIDING FORM WORK AND CENTERING FOR REINFORCED CEMENT CONCRETE WORKS INCLUDING SUPPORTS AND STRUTTING UP TO 3.30M HEIGHT FOR PLANE SURFACES AS DETAILED BELOW WITH ALL CROSS BRACINGS USING MILD STEEL SHEETS OF SIZE 90CMX60CM AND MS 10 GAUGE STIFFENED WITH WELDED MILD STEEL ANGLES OF SIZE 25MMX25MMX3MM FOR BOARDING LAID OVER SILVER OAK OR COUNTRY WOOD JOISTS OF SIZE 10CMX6.5CM SYACCED AT ABOUT 90CM CENTRE TO CENTRE AND SUPPORTED BY CASURINA PROPS 10CM TO 13CM DIA SPACED AT 75CM INTERVALS AND REMOVING THE SAME AFTER A SPECIFIED PERIOD WITHOUT DAMAGING THE R.C.C WORKS ETC., COMPLETE COMPLYING WITH			
		STANDARD SPECIFICATIONS AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS.			
	78.10 Sq.M	STANDARD SPECIFICATIONS AND AS DIRECTED BY THE	Rs.900.00 7 (Rupees nine hundred only)	1.sq.M.) (ONE SQUARE METRE)	70290.00
32	78.10 Sq.M	STANDARD SPECIFICATIONS AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (b) PLAIN SURFACES SUCH AS ROOF SLAB, FLOOR SLAB, BEAMS LINTELS, LOFTS, SILL SLAB, STAIRCASE WAIST, PORTICO SLAB AND	Rs.900.00 7 (Rupees nine hundred only)	(ONE SQUARE	70290.00
2	78.10 Sq.M	STANDARD SPECIFICATIONS AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS. (b) PLAIN SURFACES SUCH AS ROOF SLAB, FLOOR SLAB, BEAMS LINTELS, LOFTS, SILL SLAB, STAIRCASE WAIST, PORTICO SLAB AND OTHER SIMILAR WORKS	Rs.900.00 (Rupees nine hundred only)	(ONE SQUARE	70290.00





		Special repair works			PAGE - 8
5.N°	QUANTITY 2	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS 4	UNIT IN FIGURES AND IN WORDS 5	AMOUNT 6
		AGGREGATES TO BE USED SHOULD COMPLY WITH THE REQUIREMENTS OF IS STANDARDS. (NO SEPARATE PAYMENT WILL BE MADE BY THE DEPARTMENT FOR THE EXCESS USAGE OF MATERIALS).			1473622.30
	9.40 Cu.M.X	(c) IN SECOND FLOOR	Rs.8200.00 7 (Rupees eight thousand and two hundred only)	1.Cu.M. (ONE CUBIC METRE)	77080.00
3	6.30 Cu.M.	WEATHERING COURSE WITH CONCRETE BROKEN BRICK JELLY 20MM GAUGE IN PURE BURNT LIME STONE SLAKED AND SCREENED (NO SAND) OVER RCC ROOF SLAKED AND SCREENED (NO SAND) OVER RCC ROOF SLAKED WITH PROPORTION OF BRICK JELLY TO LIME (FAT LIME) BEING 32: 12 1/2 BY VOLUME WELL BEATEN WITH WOODEN BEATERS FOR GIVING THE REQUIRED SLOPE AND THICKNESS COMPLYING WITH RELEVANT STANDARD SPECIFICATION AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS	(Rupees three thousand and four hundred only)	1.Gu.M. (ONE GUBIC METRE)	7 21420.00
34	6 NOS.	SUPPLYING AND FIXING OF INDIAN WATER CLOSET WHITE GLAZED (ORIYA TYPE) OF SIZE 580MMX440MM OF APPROVED MAKE WITH ISI MARK (TO BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE) WITH PVC SWR GRADE P OR S TRAP INCLUDING CONCRETE FILLING THE SUNK PORTION WITH BRICK JELLY LIME CONCRETE PROPORTION OF BRICK JELLY TO LIME BEING 32:12½ BY VOLUME (32 CFT OF 20MM GAUGE BRICK JELLY AND 12 ½ CFT OF SLAKED LIME) (NO SAND) AND TOP 75MM THICK BRICK JELLY CONCRETE IN CC 1:8:16 (ONE OF CEMENT, EIGHT OF CRUSHED STONE SAND AND SIZTEEN OF BROKEN BRICK JELLY) USING 40MM SIZE BRICK JELLY INCLUDING PLASTERING THE SIDES OF SUNK PORTION IN CM 1:3 (ONE OF CEMENT AND THREE OF CRUSHED STONE SAND) 12MM THICK MIXED WITH WATER PROOFING COMPOUND AT 2KG/SQM AND TOP LEFT ROUGH TO RECEIVE THE FLOOR PLASTERING BUT INCLUDING ANTISYPHONAGE CONNECTION, ONE COAT OF BITUMEN FOR THE SIDES, BOTTOM AND CURING ETC., COMPLETE IN ALL FLOORS. (OTHER THAN GROUND FLOOR)	(Rupees five thousand three hundred and twenty three only)	1.NO. (EACH) X	31938.00
5	0.705 M.T.	SUPPLYING, FABRICATING AND PLACING IN POSITION OF MILD STEEL GRILLS/RIBBED TOR STEELS (WITHOUT CEMENT SLURRY) OF ALL DIAMETERS FOR REINFORCEMENT FOR ALL FLOORS INCLUDING COST OF BINDING WIFE, BENDING, TYING ETC., ALL COMPLETE AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS FOR ALL SIZES.	(Rupees eighty six thousand only)	1 M.T. (ONE METRIC TONNE)	60630.0
66	9.60 Sq.M.X	WHITE WASHING TWO COATS FOR OLD CEILING SURFACES BY USING CLEAN SHELL LIME SLAKET INCLUDING COST OF LIME, GUM, BLUE, BRUSHES INCLUDING SCAFFOLDING ETC., COMPLETE IN ALI RESPECTS AND COMPLYING WITH STANDARE SPECIFICATIONS.	(Rupees thirty three only)	1.Sq.M. (ONE SQUARE METRE)	316.8
		*			1665007.1

S-2414000) S

8

NO. OF CORRECTIONS

Special repair works at Sivakasi

S.NO	QUANTITY	DESCRIPTION OF WORK	RATE EXCLUSIVE OF GST IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN WORDS	AMOUNT
1	2	3	4	5	6
37	4 NOS	SUPPLYING AND ERECTION OF ROTATIONAL MOULDED POLYETHYLENE WATER STORAGE TANKS (HDPE CYLINDRICAL VERTICAL TYPE) FOR OUTDOOR USE HAVING CAPACITY OF 700	hundred and eighty six only)	1.NO. (EACH)	1665007.10 29544.00
		LITRES (EXCLUDING FREE BOARD) OF APPROVED BRAND (SUPERIOR VARIETY) WITH ISI MARK (MARKED IN THE TANK ITSELF) WITH TOP LID WITH PROVISIONS OF LOCKING INCLUDING NECESSARY SPECIALS AND FITTINGS FOR STORING POTABLE WATER AND MANUFACTURED WITH MATERIAL WHICH DO NOT IMPORT ANY TASTE /ODOUR/ ANY TOXIC EFFECT AND NOT TO CONTAMINATE ETC., WITH CARBON BLOCK CONTENT AND DISPERSION IN ACCORDANCE WITH RELEVANT I.S. SPECIFICATION AND AS DIRECTED BY THE DEPARTMENTAL OFFICERS ETC., COMPLETE. (THE TANK SHOULD BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)			
38 497.90 Sq.M.	497.90 Sq.M.	PAINTING THE NEW WALLS WITH TWO COATS OF OIL BOUND DISTEMPER OVER THE EXISTING PRIMING COAT OF WHITE CEMENT OF APPROVED BRAND OVER NEW CEMENT PLASTERED WALL SURFACES INCLUDING COST OF PAINTS, PUTTY, BRUSHES, WATERING, CURING, ETC., ALL COMPLETE AS DIRECTED BY THE DEPARTMENTAL OFFICERS (PAINTS AND ITS SHADE SHALL BE GOT APPROVED FROM THE EXECUTIVE ENGINEER BEFORE USE)	(Rupees one hundred and fifteen	1.Sq.M. (ONE SQUARE) METRE)	57258.50
¥		TOTAL AMOUNT (EXCLUDING GST)		1	1751809.60
		GST Amount for providing Service to Government Contract Works for the above Construction Works. (GST @ 18%)		5	315325.73
				1	

(RUPEES TWENTY LAKHS SIXTY SEVEN THOUSAND ONE HUNDRED AND THIRTY FIVE AND PAISE THIRTY THREE ONLY)

S. And mon ag

9

NO. OF CORRECTIONS